## SHIMOGA DIVISION.

[ADVERTISEMENT.

*Notification dated 14th June 1895.*

Tenders are hereby invited for restoring Belegere Wud and Channels, Channagiri Taluk. Approximate quantity of estimate are given below but they are not guaranteed.

2. The plans, estimates, schedule of rates, and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor, and forwarded in sealed covers to the Executive Engineer before the 1st July 1895.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 200 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

| *Items of work.* | | *Quantity.* |
|---|---|---|
| Earthwork cutting channel | C. Yds. | 45,212 |
| Grading channel zero and mile stones | Each. | 6 |
| Tank grade stones | Do | 69 |
| Bed grade stones | Do | 76 |
| Carriage of earth excavated from channel to raise the low parts of spoil bank | L. S. | Rs. |
| Earthwork excavated including carriage to wings | C. Yds. | 7,568 |
| Ditto draft channel | Do | 4,533 |
| Concrete | C. Ft. | 6,665 |
| Brick in mortar | Do | 6,188 |
| Rubble stone in mortar | Do | 7,767 |
| Coarsed do | Do | 5,595 |
| Burnt stone slabs | Sq. Ft. | 1,378 |
| Plastering with mortar | Sqr. | 15·00 |
| Painting with do | Do | 25·15 |
| Rough stone work | C. Yd. | 2,183 |
| Filling in jelly under apron | Do | 431 |
| Pin and other slabs | S. Ft. | 788 |
| Jungle clearing | L. S. | .. |
| Cut stone work | C. Ft. | 65· |
| Shutter and lifting gear | Each. | 3 |
| Turfing | Sqr. | 1124·25 |
| Mangalore pipe sluices | Each. | 14 |
| Retaining rough stone weirs | Do | 3 |
| Ditto masonry weirs | Do | 1 |

*N. B.*—Government materials if any at site of the work will be issued to the contractor at their booked valuation.

B. VENKATACHAR, *Executive Engineer.*

## CINCHONA FEBRIFUGE.

Cinchona Febrifuge can be purchased by all Government officers and by any one taking *six pounds* at a time, from the Superintendent, Botanic Garden, Calcutta, at the following rates :—per four-ounce tin, *Rs.* 2, *ans.* 8 ; per eight-ounce tin, *Rs.* 5 ; per pound tin, *Rs.* 10. The general public can be supplied by the Superintendent, Botanic Garden, *for Cash only*, at the undernoted rates—per four-ounce tin *Rs.* 8 ; per eight-ounce tin, Rs. 6 ; per pound tin, *Rs.* 12. This medicine is also sold by the principal European and Native druggists in Calcutta. Postage four annas per four-ounce tin, eight annas per eight ounce tin, and twelve annas per pound tin, in addition to the foregoing rates.